



Onion Valley Fuel Break

- Fuel Break
- - - Fuel Reduction 1:3,600
- Native Garden Fuel Reduction
- — ● Park/Nature Trail (roughly)

Project Details

- 2 different treatment types:
 - Fuel break (solid line on west side of project area)
 - Fuel reduction (dashed line)
- Fuel break:
 - 50' wide
 - ~85% of vegetation will be cut
 - A mosaic of islands of vegetation of various natural appearing shapes & sizes will be retained
 - Distance between islands = 2.5x vegetation height
 - No riparian vegetation will be cut, plus an additional no cut zone adjacent to riparian vegetation equivalent to the width of a mature shrub (~6')
 - Cut material will be chipped on-site or pile burned
 - No trees will be cut
- Fuel reduction:
 - ~85% of vegetation will be cut
 - A mosaic of islands of vegetation of various natural appearing shapes & sizes will be retained
 - Distance between islands = 2.5x vegetation height
 - No riparian vegetation will be cut, plus an additional no cut zone adjacent to riparian vegetation equivalent to the width of a mature shrub (~6')
 - Cut material will be chipped on-site or pile burned
 - No trees will be cut
 - Any fuel reduction work done within the Native Garden area identified on the map will be done under the supervision of Native Garden representatives
- All fuel reduction work will be completed outside of nesting bird season, between September 15 & March 15, to the extent possible. Work may be done during nesting bird season if surveys are conducted prior to commencement of operations are no nesting birds are identified.